



American

CONCRETE PUMPING

319★350★6391




***“Serving our Customers
with American Pride”***



WHY PUMP OR CONVEY MATERIALS

- **Labor Savings:** In the competitive market of today, precision placement can reduce the number of people required to place materials.
- **Speed:** Our pumps have a manufacturer rating of up to 200 cubic yards per hour and our telebelts have a manufacturer rating of up to 360 cubic yards/tons per hour.
- **Reduce Excavation Cost:** Leave the backfill near the excavation site so you don't have to move it twice. The ready-mix trucks don't need to get close to the excavation site when you pump or convey.
- **Insulated Concrete Forms:** (ICF) are a growing trend in residential construction. The steady flow of concrete from a pump is a faster, more efficient way to complete a job of this type.

- 
- **Community Relations:** Ready-mix trucks stay on the pavement when a pump or conveyor belt is used eliminating muddy residential streets.
 - **Cost Savings:** Concrete pumps and belts are the fastest and most efficient method for placing concrete, allowing more completed jobs per day.
 - **System:** We can add system to pump concrete hundreds of feet from the ready-mix truck by attaching the system to the concrete pump. The system is available upon request.
 - **Rock Hopper:** Use our rock hopper, in addition to one of our telebelts, to place larger quantities of dry materials at a faster pace.
 - **Other Materials:** The conveyor places sand, lime, mulch, rock (up to 4"), and high slump concrete mixes up to 130' away from the truck with a manufacturer rating of up to 360 cubic yards per hour.

WHY PLACE WITH US?

Since 1997 American Concrete Pumping has done what it takes to grow with our customers. Our ever growing fleet of equipment consists of "Z" booms and roll & fold concrete pumps that range from 32 meter through 65 meter. In addition to our fleet of concrete pumps, we have 80', 110' and 130' telebelts. To round out our fleet we have dump truck conveyors and line dragons, as well as our recently acquired trailer pump. We will continue to do what it takes for our customers and their growing needs.


Our experienced operators are ACPA certified and undergo yearly training.

If you have any questions or special projects for us to look at, please call sales at 319-350-3911. Call dispatch to schedule a job at 319-350-6391. Ray, the owner is also available to answer questions and/or look at special projects. Call him at 319-350-2241.



CONTRACTOR TIPS


Before the Equipment Arrives

- Overhead lines are extremely dangerous! Please do not ask our operators to unfold the boom within **20-feet** of any power lines.
 - **One-to-One Rule.** For every foot of excavation depth, we require one foot setback from the hole for set-up.
 - Review hand signals with pump operators before placing concrete.
 - We recommend the use of hardhats and safety glasses when placing concrete.
- 


32 METER



106' 4 Section Boom
85' Reach Off Front Bumper



32 METER




24' 9"
Unfolding
Height


32Z METER



104' 6" 4 Section "Z" Boom
83' 8" Reach Off Front Bumper



32Z METER




25' 3"
**Unfolding
Height**


38Z METER



123' 5 Section "Z" Boom
98' 6" Reach Off Front Bumper



38Z METER




23' 11"
**Unfolding
Height**


39 METER



127' 4 Section Boom
105' Reach Off Front Bumper



39 METER




29' 2"
Unfolding
Height


46 METER



149' 4 Section Boom
128' 10" Reach Off Front Bumper



46 METER




39' 6"
Unfolding
Height


47Z METER



151' 3" 5 Section "Z" Boom
128' 2" Reach Off Front Bumper



47Z METER




31' 2"
Unfolding
Height


52Z METER




169' 5 Section "Z" Boom
148' Reach Off Front Bumper



52Z METER





One-Sided Support




58 METER




187' 10" 4 Section Boom
164' Reach Off Front Bumper



58 METER



56' 5"
Unfolding
Height




65 METER




210' 8" 5 Section Boom
187' Reach Off Front Bumper


S 65 SX EASy Flex Outrigging Options:



65 METER




50' 2"
Unfolding
Height




TB 80




46.6' Vertical Reach 75' 7" Reach Off Rear Bumper




TB 80




TB110



60' 2" Vertical Reach 106' Reach Off Rear Bumper




TB110




TB130



68' 3" Vertical Reach
126' 6" Reach Off Rear Bumper



TB130



SHOOTER



Distance Diagrams


The CAS Difference

Coverage

CAS has approx. 2 times greater coverage*

The CAS Difference – Area Coverage

Other Conveyor Trucks – Area Coverage



Production

Higher volumes at greater distances



Able to place rock, sand, lime and mulch

DUMP TRUCKS



LINE DRAGONS



Placer Max Weight 490 lbs. per wheel
Dragger Max Weight 296 lbs. per wheel



LINE DRAGONS

Powered by 12 horsepower gasoline engines, the Line Dragons will easily maneuver over rebar grid, radiant heat lines, nelson studs, floor decking or other prepared surfaces. Weighing in at about 1,415 total pounds, means less weight per square inch of footprint than most manual laborers. The 'Placer' is attached to the end of the delivery line and places concrete where you need it while the 'Dragger' is 20' away keeping the excess line out of the pouring area.

Our machines move forward, backward, left, right or oblique. The placing boom swings 360 degrees making all areas accessible to the Placer. Both machines are radio-controlled with fully hydrostatic controls for ease of operation at a safe distance making your employees more efficient with huge savings.

Visit our website for more information or to see a video of the system in use.

TRAILER PUMP

Gross Weight: 8,750 lbs.
100 Horsepower
50 Cubic Yards Per Hour
Maximum Aggregate: 1.5"



CONTACT



319★350★6391

152 W. Union St.
Manchester, Iowa 52057
acpi@americanconcretepumpingia.com

OWNER

Ray Philippon..... 319-350-2241

SALES

Chris Heims..... 319-350-3911

DISPATCH..... 319-350-6391

6 a.m. - 6 p.m.

Monday-Friday CST

7 a.m. - 12 p.m.

Saturday CST

SHOP LOCATIONS

Manchester, IA

2240 180th Ave.

Cedar Rapids/Iowa City

Farley

Grand Mound

Visit us at:

www.americanconcretepumpingia.com



We're also on Facebook & Instagram!

Minority Owned



CONCRETE PUMPING
9-350-6391

AMERICAN

AMERICAN

***“Serving our Customers
with American Pride”***